

Case Study

Date of Project: October 2022
Applicator: Wilsons Pipeline Solutions
Client: City of Gold Coast
Location: Gold Coast, Australia
Pipe: 100mm (4") Asbestos Cement
Length Lined: 400 meters

Project Details

A failing pressure release valve was causing this 400 meter section of pipe to spike in pressure up to 12 bar (1200kPa).

The pipe was cleaned by high pressure water jetting and lined with 3mm of Resiline 320 in a single pass, preventing further deterioration and retaining existing strength in the pipe wall.



For more information please visit www.resiline.co.uk